



### Bat Access Panels

Suitable products: Ibstock Enclosed Bat Box 'C' (left); and Habibat Bat Access Panel (right)

### Tree Mounted Bat Boxes

Suitable products: Schwegler 1FF, Greenwoods Ecohabitats bat boxes and Schwegler 1FD

Single Crevice Bat Box

Box Specifications in CM:  
 Height x Width x Depth  
 External 44 x 23.5 x 6  
 Internal 42 x 21.5 x 2  
 Volume: 1.47 litres

### House Sparrow Nesting Terrace

Suitable products: 1SP Schwegler House Sparrow Terrace

### Swift Nest Box

Suitable products: Ibstock Eco-habitat for Swift (left) and Manthorpe Swift Nesting Box (right)

### Small Bird Boxes

Suitable products: Schwegler 2M (left) and Schwegler 1N deep nest box (right)

### Key to Map Symbols

- Site boundary
- Bat access panel [2]
- House sparrow nesting terrace [2]
- Small bird nest box [2]
- Swift nest box [1]
- Tree mounted bat box [1]
- Hedgehog gaps [17]
- 2203-PL-03 rev F PROPOSED SITE PLAN A1.dxf

Plot No.	Box type	Aspect
3	House sparrow nesting terrace	NE
4	Bat access panel	S
6	Swift nest box	N
7	House sparrow nesting terrace	N
7	Tree mounted bat box	S
7	Small bird nest box	NE
7	Small bird nest box	NE
8	Bat access panel	W

**Notes:**  
 Bat and bird boxes available from NHBS Ecology ([www.nhbs.com](http://www.nhbs.com)), Wild Care ([www.wildcare.co.uk](http://www.wildcare.co.uk)) and / or Greenwood's Ecohabitats ([www.greenwoodsecohabitats.co.uk](http://www.greenwoodsecohabitats.co.uk))

Gaps for hedgehog access to be provided at all plot boundary fencing.

All boxes (bat and bird) are to be positioned so they are not directly over windows and doorways to avoid and minimise nuisance via droppings.

Small bird boxes (including house sparrow) should be installed at least 2 metres above ground. Swift boxes and bat boxes / access panels should be installed at least 4 metres from the ground.

RSPB advice states that bird boxes should ideally be sited facing north to east, to avoid exposure to direct sunlight, which may cause overheating of chicks in the nest.

Bat boxes can be sited at a variety of aspects, although boxes facing south are more likely to be suitable for use by maternity colonies as they will gain additional heat from the sun throughout the day.

**Figure 1:**  
 Plan to Show Recommended Locations for Bat and Bird Boxes and Hedgehog Gaps

**Project Name:**  
 Northcote Road, Langho BB6 8BG

**Central Grid Ref:**  
 SD 70748 34570

**Reference No.**  
 ERAP Ltd. 2022-019c

**Version & Date:**  
 v1 (RB) 09/01/2024

**Scale:** 1:400 at A3

Z:\Current Jobs\2022\2022-019 Northcote Road, Langho\9. 2022-019c Bat and bird box plan\2. Maas\ERAP 2022-019c.aas

**ERAP Ltd**  
 Consultant Ecologists

Building N2, Chorley Business and Technology Centre  
 East Terrace, Euxton Lane, Euxton, Chorley, PR7 6TE  
 Tel: 01772 750 502 Email: [mail@erap.co.uk](mailto:mail@erap.co.uk) Website: [www.erap.co.uk](http://www.erap.co.uk)