

Methodology Statement

As stated in the application form submitted, work has already been completed via the methods described below.

The hand basin has been installed in the left-hand corner of the room, as entering from the doorway. It is of a traditional look, in-keeping with the building's character. It has been installed with a mixer tap, operated via a handsfree lever, and is connected to a hot and cold-water supply. There is a deep seal trap on the waste which disperses into the existing sewer system.

Tiling has been carried out on the external wall by the window. Light grey subway tiles have been applied using the standard method, with tile adhesive and then sealed with grout. Approximately 14 square metres (sq mtr).

All walls, including the ceiling have been painted with quality emulsion.