



@ansell_lighting



ansellighting



Ansell Lighting







ansell_lighting

Latina Wall Lantern

Latina Wall Lantern PIR Black

Code: ALWLLED/PIR/BL

Category	Wall Lights
Application	Hospitality, Outdoor, Residential, Retail
Specification	Architectural



PRODUCT FEATURES

- LED light bar for uniform light output
- Unique design provides installer with option of top arm or bottom arm mounting, without the need of additional wiring (PIR version bottom arm mounting only)
- PIR option for convenience and security. Incorporates manual override option
- Non-dimmable
- LED light bar for uniform light output
- Textured polycarbonate finish and tinted lens
- Colour matching PIR lens ensures discreet appearance

GENERAL INFORMATION	
Wattage	8W
Lumens Delivered	550lm
Lm/W	68lm/W
Beam Angle	360
CRI	80
CCT	3000K
Input	220/240V
Operating Temp	-10°C - 40°C
SDCM	6
Product Weight without Packaging	0.61 kg

TECHNICAL INFORMATION	
Light Source	LED
Colour / Finish	Black
IP Rating	IP65
Class Protection	2
Internal / External	External
Surface / Recessed / Suspended	Wall
Lumen Depreciation	L70 60,000h
Warranty (Years)	3
CE Mark	Yes
Height	410 mm
Accessories	ALWL/CBB

