



PLANTING SCHEDULE

Woodland Planting

The planting indicated to the West boundary of the site (adjacent to the existing hedge) is to consist of a mixture of bare root whips, planted with a spacing of 1 -1.5m. Native species mixture consisting of 50% Oak, 20% Silver Birch, 10% Hazel, 10% Holly and 10% Rowan to be used.

All trees to have spiral rabbit guards.

New Trees

62 no new trees to be planted within the site and to the South/ East boundaries as indicated. Trees planted to be as follows:-

- | | |
|------------------------------------|-------------------------|
| 18 no Acer Campestris (Maple) | HS 12-14 RB |
| 4 no Alnus Glutinosa (Alder) | HS 12-14 RB |
| 9 no Betula Pendula (Silver Birch) | STD 8-10 CG |
| 16 no Carpinus Betulus (Hornbeam) | HS 12-14 RB |
| 2 no Prunus Avium (Wild Cherry) | EHS 14-16 RB |
| 4 no Quercus Robur (English Oak) | 2.1 - 2.4m high Fthd CG |
| 9 no Sorbus Aucuparia (Rowan) | HS 12-14 RB |

All trees to have spiral rabbit guards.

Landscaping and Bat/ Bird Box Locations

All grassed areas to be seeded with PRO 25 low maintenance mix supplied by DLF Trifolium grass seed manufacturerd by DLF Trifolium , and spread to their recommended rates.

3 no bat roosting sites indicated with a ★

7 no nest boxes indicated with a ★

KEY

- Grass
- Gravel
- Paths
- Mulch/ Bark

REV B - Drawing updated. LFR 20.06.24
REV A - Drawing updated. LFR 18.06.24

Client A I Land Ltd		
Project Proposed Extension to Mitton Road Business Park Whalley		
Drawing Title Proposed Landscaping Layout incorporating Locations of Bat Roosts and Bird Nest Boxes		
Scale 1:500 @ A2	Date June 2024	Drawn LFR
READ DESIGN LTD		
102 - 08_B		