



GENERAL NOTES

1. This drawing is the copyright of tpm landscape Ltd and cannot be reproduced in any form without the consent of the company.
2. This drawing is to be read in conjunction with detail landscape drawings, details and specification.
3. This drawing is to be read in conjunction with all relevant Architects', Engineer's, Specialists, Bills of Quantities and Specifications.
4. The insertion of any firm or proprietary brand on this drawing is an indication of the class or quality required and does not exclude the use of alternative materials that are equal in performance, quality and appearance, provided that they have been approved in writing by the Landscape Architect.
5. The Contractor is responsible for accurately ascertaining the position of underground services and responding to all relevant service easement requirements.
6. All dimensions are in millimetres unless stated otherwise, for the purposes of construction this drawing must not be scaled and only written dimensions used. Written and scaled dimensions to be checked on site, any discrepancies reported prior to work commencing. IF IN DOUBT PLEASE ASK.
7. All work and materials are to be in accordance with the relevant British Standards and Code of Practice.
8. All Proprietary products are to be used strictly in accordance with the manufacturer's instructions and details.

ECOLOGICAL ELEMENTS

- Proposed Two-crevice Bat Box
- Proposed 28mm Entrance Bird Box
- Proposed 45mm Entrance Bird Box
- Proposed Oval Entrance Bird Box
- Proposed Hedgehog Highway Paths
Gap in boundary fencing to be provided

REVISION NOTES

Rev	By	Description	Date
J	JW	Additional bat box location revised	15.08.24
I	JW	Bat boxes added to the barn	07.08.24
H	JW	Updated in line with client's comments	16.04.24
G	JW	Updated in line with client's comments	05.04.24
F	JW	Retaining wall and embankment added as per engineer's drawing	01.03.24
E	AJ	Ecological enhancements added	17.10.23
D	TS	Revised in line with the Client's comments (Hedge removed)	15.08.23
C	TS	Revised in line with the Client's comments (Changed in plots 13/14, 19/20, 23/24 and hedgerow along boundary)	03.08.23
B	TS	Revised in line with the Client's comments	19.07.23
A	TS	Revised in line with the latest architect's layout	29.06.23

LEGEND

SOFT LANDSCAPE

- Existing Tree and Hedgerow to be Retained**
Trees to be retained and protected in line with BS5837:2012.
- Existing Tree and Hedgerow to be Removed**
- Proposed Trees in POS**
Extra Heavy Standard, 14-16cm girth, 4.5-6.25m high to be planted with a double timber stake secured with a rubber tree tie.
- Proposed Ornamental Trees in Front Gardens**
Heavy Standard, 12-14cm girth, 3.5-4.25m high to be planted with a double timber stakes secured with a rubber tree tie.
- Small Ornamental Tree/Large Shrub**
Select Standard trees, 10-12cm girth, 3-3.5m high or large shrub 30-50L to be planted with a single timber stake secured with a rubber tree tie.
- Orchard Tree**
Select Standard trees, 10-12cm girth, 3-3.5m high to be planted with a single timber stake secured with a rubber tree tie.
- Ornamental Shrub Planting**
Proposed shrubs and flowering herbaceous plants to be planted as 5-10L pots at 3-5 per sq.m. planted with feature specimen, 10-12L pots.
- Proposed Native Shrub Mix**
Bare root stock, 60-80cm, planted at 2-3m², in groups of 3-5. Plants to be protected with spiral guards where necessary.
- Proposed Hedge**
Evergreen hedge to be planted in 10L containers at a rate of 3-4 per lin. metre.
- Proposed Native Hedgerow**
Proposed Hedgerow to be planted as 100-120cm high whips in a double staggered row at 400cm spacings.
- Proposed Wildflower Grass Seeding of Undisturbed Ground**
To be Emorsgate EM2F Standard General Purpose Wild Flowers Mix, supplied by Emorsgate or similar approved. Mixture containing 100% native wild flowers for sowing into existing grass. Sowing rate 1.5g/m².

- Proposed Amenity Grass**
Front gardens to be turf. Back gardens to client specification. POS Grass to be seeded
- Existing Garden to Farm**
To be retained and enhanced
- HARD LANDSCAPE & FEATURES**
- Proposed Tarmac for Driveways**
- Proposed Flag Paving**
- Proposed Gravel**
- Proposed Raised Planting beds**
Existing raised planting to be replaced.
- BOUNDARY TREATMENT**
- Proposed Landscape Green Screen**
To planting plan/architect's details.
- Masonry Retaining Wall**
0.45m to 1.4m high, refer to engineer's drawing
- Infill Concrete Cavity Retaining Wall**
0.8m to 1.15m high, refer to engineer's drawing
- PC Flag on edge/concrete gravel board**
0.3m max. high, refer to engineer's drawing

Client
Pringle Homes

Project
Crow Tree Farm

Description
Landscape Layout

Status
For Approval

Scale @ A2
1:500

Drawn
TS

Checked
KH

Date
03.11.22

Job number
4265

Drawing number
101

Revision
J