

4962.002

11<sup>th</sup> December 2024

### **Thorneyholme RC Primary School, Dunsop Bridge Proposed Fencing Photos & Specification**

The new weld mesh fencing & gates to the front boundary is to match exactly the existing weld mesh fencing to the side boundary, comprising the following specification.

- 2m high 656 twin mesh fencing, 2m high x 2.51 wide
- 200 x 50 apertures, comprising 2no. 6mm dia. horizontal wires & 1no. 5mm vertical wire
- 60 x 60 box section posts & framing galvanised
- Polyester powder coated, colour to be green RAL 6005



Existing fencing photo A



Existing Fencing Photo B