


existing barn conversion

Studio Conversion



2 Proposed South Elevation  
Scale 1 : 50



3 Proposed East Elevation  
Scale 1 : 50

**Capacity For Change**  
Currently the 'Studio' external walls are of blockwork construction which is in keeping with the rest of the site and surrounding buildings. Insulation and random stone will be added to the outer skin. This will enhance U-Values to be Building Regulation compliant and preserve a site wide aesthetic.

**Minimising Alterations and Loss**  
Existing openings have been utilised. Please refer to elevations to see any opening alterations.

**Walls / Openings**  
Internal rooms have been planned around existing openings

**Windows and Doors**  
Both windows and doors will be repaired rather than replaced where appropriate.

**Repairing Roofs**  
New roofs only to be used if necessary (determined by survey)

**Roof Lights**  
Roof lights have been carefully positioned to the northern slope. They will be flush to the roof and of a conservation aesthetic (VELUX GGL).

**Drainage/RWP**  
Ideally cast iron or extruded aluminium drainage is preferred

**Heating**  
Radiators not effective in farmhouses and therefore underfloor heating would be preferred.  
Wood burner flue and SVPs protruding through the roof to be painted with non-reflective paint.

Contractors are not to scale dimensions from this drawing.

Rev	Description	By	Date
P1	Planning Issue For Review		06.09.24
P2	Planning Issue		25.09.24
P3	Dimensions added		09.12.24
P4	Rooflights amended following Planning comments		02.04.25

#### Proposed / Existing Materials


**External Walls:**  
Proposed natural random stone or existing made good and re-pointed as required  
Stone quoins (where present)

**Roof:**  
Slate ridge vent  
Natural slate ridge tiles  
Natural slate roof tiles  
Black painted timber fascia board with black half round gutter and downpipe


**Doors and Windows:**  
Timber frame doors  
Timber frame windows

existing barn conversion

Studio Conversion



1 Proposed Ground Floor Plan  
Scale 1 : 50



7 Proposed Roof Plan  
Scale 1 : 50

**MC AU** Modern City Architecture & Urbanism  
Avenue HQ  
17 Mann Island  
Liverpool  
L3 1BP  
t: 0161 974 7203  
e: info@mcau.co.uk  
www.mcau.co.uk

Client  
FI Real Estate Management


Project  
Blackmoss Farm, Studio

Description  
Blackmoss Farm Studio, Proposed Plans, Sections and Elevations


Status  
Stage 3 Planning  
Job Number  
1243-MCAU  
Drawing Number  
P.03-ST-011  
Scale  
1 : 50  
Date  
Sep 24  
Revision  
P4  
Drawn By  
JT

Copyright Modern City Architecture & Urbanism Ltd


Studio Conversion



5 Proposed Cross Section A-A  
Scale 1 : 50



4 Proposed North Elevation  
Scale 1 : 50



6 Proposed Cross Section B-B  
Scale 1 : 50