

HD2000 Polymer Drainage Channel

[PRODUCTS](#) » [DRAINAGE CHANNEL RANGE](#) » [HEAVY DUTY POLYMER CONCRETE DRAINAGE CHANNEL](#) » [HD2000 POLYMER DRAINAGE CHANNEL](#)

HD2000 is a 200mm polymer concrete drainage channel has a nominal width of 200mm for load class applications up to F900.

The HD2000 has an integral cast iron edge rail for strength under extreme dynamic loading. The lightweight construction of polymer concrete reduces installation time and manpower required on site.

- Channel sections for a linear fall (base fall 0.5%) and no fall
- Also with integral outlet connector
- F900 200mm drainage channel for airports, ports and industrial areas
- D400 200mm drainage channel for car parks, industrial and commercial units

If you require any assistance or more information please contact us by phone on 01603 488700 or by email sales@althon.co.uk


[Select PDF & CAD Files](#)

[Download Datasheets](#)

Gratings 2000		
Class D 400	ductile iron cover	solid
	ductile iron slotted grating	slot width 18/200 mm
Class E 600	ductile iron wave grating	mesh width 23/19 mm
Class F 900	ductile iron slotted grating	slot width 17/195 mm



Load classes



Product Name	Length	Min / Max Height	Channel / Overall Width	Material
HD2000 Polymer Drainage Channel	1000mm	280 - 380mm	200 - 240mm	Polymer