

Applicant

9th July 2025

Little Town Farm
Chipping Road
Thornley
Preston
Lancashire
PR3 2TB

Application No. 3/2025/0284.

To Whom

1. Footpath specification to clarify. See example pictures attached.

Footpath as per the application drawing.

Specification:-

Excavation, Topsoil, Sub-base

150mm deep consolidated hardcore filled

Concrete kerb edges to both sides nominally 70 lm run.

Sub-base, tarmac fill 100mm thick

50mm tarmac topping flush to kerb edging finished.

2. Concrete Track

Finished width – 7.0m wide x 70 lm long

Nominal 200mm thick reinforced concrete track, to match existing track at the farm End. Track to be laid in 2 strips nominally 3.5m wide. On completion the finished track will be 7.0m wide concrete roadway, each side edged by pre-cast concrete kerb edgings.



