

Kirk House  
Rear Gutter and Repointing East Gable - Method Statement

Location:

Gutter – To the East elevation of 1950's rear extension.

Gable – East elevation of the original Georgian house.

Method Statement:

Gutter

Remove existing upvc gutter and dispose

Install black half-round aluminium gutter

Fix using brackets to fascia board.

Re-pointing

Rake out joints to a minimum depth of 25-40mm or double the joint height, using hand tools only.

Repoint in NHL3.5 1:3 mortar (using sharp sand).

To be finished flush or slightly recessed.

Keep damp and protected for appropriate time.

Existing



Proposed



Half-round aluminium gutter



Kirk Mill – stone and pointing to front facade