


## DATASHEET



### WAD12ABK

230V IP65 2 x 6W LED Adjustable Up and Down Wall Light Black - 3000K

[www.mlaccessories.co.uk](http://www.mlaccessories.co.uk)



MLA PART CODE	WAD12ABK
DESCRIPTION	230V IP65 2 x 6W LED Adjustable Up and Down Wall Light Black - 3000K
NET WEIGHT (KG)	0.76
FINISH	Matt Black
DIFFUSER	Prismatic
DIMENSIONS (MM)	Height - 125 Width - 100 Projection - 100
CONSTRUCTION	Construction - Die-cast aluminium
CLASS	I
IP RATING	IP65
WATTAGE (W)	2 x 6
LAMP TECHNOLOGY	SMD LED
LAMP INCLUDED	Yes
LUMENS (LM)	2 x 300
LUMENS LIGHT SOURCE ONLY (LM)	2 x 580
LUMEN TOLERANCE	5%
EFFICACY (LM/W)	107.8
CIRCUIT WATTAGE (W)	10.8
CCT	3000K
LIGHT COLOUR	Warm White
CRI	>80
SDCM	<6
RUNNING CURRENT (A)	0.065
DISPLACEMENT FACTOR	>0.5
SVM	0.18
PST-LM	0.13
BEAM ANGLE (DEGREES)	90
LIFE SPAN (HRS)	35,000

<b>L70B50 LIFESPAN (HRS)</b>	30,000
<b>LED COMPATIBLE</b>	Yes
<b>DIMMABLE</b>	No
<b>OPERATING TEMPERATURE</b>	25°C
<b>INPUT VOLTAGE</b>	230V 50Hz
<b>CABLE GLAND INCLUDED</b>	No
<b>WARRANTY</b>	3year(s)
<b>MANUFACTURED IN ACCORDANCE WITH</b>	BS EN 60598
<b>ORIGIN OF MANUFACTURE</b>	China
<b>DECLARATION OF CONFORMITY (HELD ON FILE)</b>	Yes
<b>EAN</b>	5056270866346

Date Created: 16/03/2026 15:38

