



SPECSAVERS CLITHEROE

Our ref: P2507114

TECHNICAL SPECIFICATION & PRICING SHEET

PRODUCT : ACOUSTIC LOUVRED PANELS WITHIN ENCLOSURE

QUANTITY REQUIRED : 1off

EXTERNAL DIMENSIONS : 1500mm wide x 2,600mm high

ACOUSTIC PERFORMANCE : Acoustic Louvre Performance Data:

Louvre			Sound Reduction (dB) at Octave Band Centre Frequency (Hz)							
Depth	Style	Product Code	63Hz	125Hz	250Hz	500Hz	1kHz	2kHz	4kHz	8kHz
150mm	Single Bank	WA-ACL-150SB	4	4	6	8	10	11	11	10

: Wakefield Acoustics range of acoustic louvres has been independently tested to BS EN ISO 11546-1:2009 at Salford University.

CONSTRUCTION : The acoustic louvres are to be provided in modular form.
The acoustic louvres are to be 150mm deep (product ref: WAL-ACL-150SB) and are constructed from pre-galvanised sheet steel outer casing, containing horizontal blades containing mineral wool acoustic insulation, retained by perforated sheet.

EQUIPMENT LOCATION : External.

FINISH : Acoustic Louvres to be Powder coated to a WAL standard RAL colour.
Support framework to be mild steel, hot dip galvanised.

LEAD TIME : 12-14 working weeks from receipt of order, subject to drawing approval being received within 1-2 weeks from submission.
Delivery lead time is based on our current capacity and is subject to confirmation at time of order placement.



t. +44 (0) 1924 418 940
f. +44 (0) 1924 418 950

Flush Mills, Westgate
Heckmondwike, West Yorkshire
WF16 0EN, UK
e. noise@wakefieldacoustics.co.uk
w. www.wakefieldacoustics.co.uk