



Planting Schedules

Standard Tree Planting Schedule

Drawing Code	Name	Form	Age	Girth (cm)	Height (cm)	Clear stem (cm)	Root condition	Breaks	Nr of Trees
Ac	<i>Acer campestre</i>	Standard (heavy)	3x	12-14	300-350	175-200	RB	5	1
la	<i>Ilex aquifolium</i>	Standard (Standard)	3x	8-10	250-300	150	C/RB		2
Sa	<i>Sorbus aucuparia</i>	Standard (heavy)	3x	12-14	300-350	175-200	RB	5	2
Total									5

Fruit Tree Planting Schedule

Drawing code	Name	Form	Age	Container Size (L)	Height (cm)	Root condition	Number of Trees
A 'B'	Apple 'Braeburn'	M9 Rootstock	1 year Maiden	12L	100-200cm	C	1
A 'BS'	Apple 'Bramley's Seedling'	M9 Rootstock	1 year Maiden	12L	100-200cm	C	1
P 'V'	Plum 'Victoria'	M9 Rootstock	1 year Maiden	12L	100-200cm	C	1

Mixed Species Native Hedgerow Planting

Plant name	Common Name	Height (cm)	Root Condition	Number of times Transplant (min)	Form	Length (lin.m)	Total Plants/lin.m	Total No. Plants
Hedgerows (Double staggered row. 5 per m)								
<i>Acer campestre</i>	Field Maple	60-80	B	1+1	Branched	1	5	5
<i>Corylus avellana</i>	Hazel	60-80	B	1+1	Branched	1	5	5
<i>Crataegus monogyna</i>	Hawthorn	60-80	B	1+1	Transplant Leader and laterals	10	5	50
<i>Ilex aquifolium</i>	Holly	60-80	B	1+1	Transplant	6	5	30
<i>Prunus spinosa</i>	Blackthorn	60-80	B	1+1	Transplant	2	5	10
<i>Rosa canina</i>	Dog Rose	40-50	B	1+0 or 1/1	Branched	1	5	5
Total							21	105

FOR PLANNING

Hazelmere, Longridge Road, Hurst Green
Lancashire. BB7 9QP

Tree & Hedge Planting Plan and Schedules

SCALE: 1/250 @ A3 DATE: March 26

DRAWING: M755/HAZ/LAND/01

