



Timber Sash Window Drawing Notes

1. Proposed windows to be traditional timber vertical sliding sash windows.
2. Frames and sashes to be painted timber construction, finished externally in RAL 7013.
3. Windows to be recessed within the external stone reveal to provide a traditional appearance appropriate to the existing building and surrounding context.
4. Window proportions to follow a traditional sash arrangement with slim-profile timber members.
5. Glazing to be double glazed, subject to final manufacturer specification.
6. Window opening method to be by vertically sliding upper and lower sashes.
7. Final ironmongery, weather seals, trickle ventilation and glazing specification to be confirmed by the window manufacturer.
8. All timber windows shall be installed in accordance with the approved details and thereafter maintained.
9. Any minor technical variation required by the final window manufacturer shall retain the approved general appearance, material, colour, reveal position and opening method.

1 SASH WINDOW

SCALE: 1 : 20

Rev.	Remark	Date