

To install and level the chassis the installation team will, below each foundation pad (foot) dig down until the ground is compacted. They will then fill the hole with compacted gravel allowing the composite pad to rest on this compacted pillar.

On the QCB the feet are pitched at 1.22mt (4ft) intervals along the front and rear.

On the QC6 they are pitched at 1.0mt (3ft) along all sides.

The locking nuts allow the studio to be raised / lowered to achieve a level floor area and can take into account a fall in the land of 250mm. (1.0 metre can be catered for with the addition of leg support braces.)

When levelled Booths require a 50mm (2") gap all around the studio to allow for a free flow of air to maintain the integrity of the floor base.

