





- WHEN ALL RELEVANT DOCUMENTS HAVE BEEN RETURNED, DEPOSIT PAYMENT HAS BEEN RECEIVED AND SURVEY COMPLETED. (SUPPLY AND INSTALL)

Position	Quantity	Description
001	3 Pcs	Window Elements Window Elements
Exterior view 		Window Elements 610 mm x 2850 mm, Consisting of four Fixed Fields and a Top Hung Window. System: SMA Alitherm Heritage Finishes: Profiles: BL Glazing: 4 x 2x4mm TGH Low E, Climaguard A+, Reeded Argon filled, Thermal black spacer bar 1 x 2x6mm Low E, Climaguard A+, SATIN & SHAPED TGH, Argon filled, Thermal black spacer bar CONTAINMENT Profiles: Frame: W20015 OUTERFRAME Mullion: W20035 MULION TRANSOM FOR BEADS+STAYS Window Vent: W20025 SASH / VENT FOR W20015/20035 Window Hardware: ALITHERM HERITAGE 47, H/H
002	9 Pcs	Window Elements Fixed field
Exterior view 		Window Elements 610 mm x 2850 mm, Consisting of five Fixed Fields. System: SMA Alitherm Heritage Finishes: Profiles: BL Glazing: 4 x 2x4mm TGH Low E, Climaguard A+, Reeded Argon filled, Thermal black spacer bar 1 x 2x6mm Low E, Climaguard A+, SATIN & SHAPED TGH, Argon filled, Thermal black spacer bar CONTAINMENT Profiles: Frame: W20015 OUTERFRAME Mullion: W20035 MULION TRANSOM FOR BEADS+STAYS
003	1Pcs	Window Element Window Element
Exterior view		

Position	Quantity	Description
		Window Element 610 mm x 1520 mm , Consisting of two Fixed Fields and a Top Hung Window. System: SMA Alitherm Heritage Finishes: Profiles: BL Glazing: 3 x 2x4mm TGH Low E, Climaguard A+, Reeded Argon filled, Thermal black spacer bar Profiles: Frame: W20015 OUTERFRAME Mullion: W20035 MULLION TRANSOM FOR BEADS+STAYS Window Vent: W20025 SASH / VENT FOR W20015/20035 Window Hardware: ALITHERM HERITAGE 47, H/H
004	1Pcs	Window Element Fixed field Window Element 610 mm x 1650 mm , Consisting of three Fixed Fields. System: SMA Alitherm Heritage Finishes: Profiles: BL Glazing: 2 x 2x4mm TGH Low E, Climaguard A+, Reeded Argon filled, Thermal black spacer bar 1 x 2x6mm Low E, Climaguard A+, SATIN & SHAPED TGH, Argon filled, Thermal black spacer bar CONTAINMENT Profiles: Frame: W20015 OUTERFRAME Mullion: W20035 MULLION TRANSOM FOR BEADS+STAYS
		
005	1Pcs	Window Element Window Element Window Element 610 mm x 1650 mm , Consisting of two Fixed Fields and a Top Hung Window. System: SMA Alitherm Heritage Finishes: Profiles: BL Glazing: 2 x 2x4mm TGH Low E, Climaguard A+, Reeded Argon filled, Thermal black spacer bar 1 x 2x6mm Low E, Climaguard A+, SATIN & SHAPED TGH, Argon filled, Thermal black spacer bar CONTAINMENT Profiles: Frame: W20015 OUTERFRAME Mullion: W20035 MULLION TRANSOM FOR BEADS+STAYS Window Vent: W20025 SASH / VENT FOR W20015/20035 Window Hardware: ALITHERM HERITAGE 47, H/H
