

Tree Number	Species	Age Class	DBH	Height (crown height)	N	E	S	W	Condition	Life Expectancy	Physical Description	Comments	Managment Recommendations	RPA offset from stem.	Category Rating
T1	<i>Acer pseudoplatanus</i> (Sycamore)	M	430 300 240	12(3)	6	6	6	6	Good	20+	Offsite tree no access to stems estimated dbh. Recently crown lifted.	Stem divides below 1.5m.	None	6.92	B1
T2	<i>Acer pseudoplatanus</i> (Sycamore)	M	220	10(2)	2	3	3	3	Fair	20+	Small tree set in hedgerow on Eastern site boundary.	None	None	2.64	B1
T3	<i>Acer pseudoplatanus</i> (Sycamore)	M	270	10(2)	4	4	4	4	Fair	20+	Small tree set in hedgerow close to Eastern boundary.	Stem divides above 1.5m. Included bark present in fork.	None	3.24	B1
T4	<i>Betula pendula</i> (Silver Birch)	M	400	14(3)	4	4	4	4	Good	20+	Offsite garden ornamental tree. No access to stem, estimated dbh.	Unable to inspect stem due to Ivy. Stem divides above 1.5 m.	None	4.8	B1
T5	<i>Sorbus aucuparia</i> (Rowan)	M	200	8(3)	1	2	1	2	Good	20+	Offsite garden ornamental tree no access to stem, estimated dbh.	None	None	2.4	B1
T6	<i>Fagus sylvatica</i> 'Purpurea' (Copper Beech)	M	300	12(2)	5	5	5	5	Fair	20+	No access to stem due to dense epicormic growth. Set in old raised bed.	Epicormics on stem. Stem divides above 1.5m.	None	3.6	B1
T7	<i>Fraxinus excelsior</i> (Ash)	M	290	13(6)	3	3	3	3	Fair	10+	Set in old raised bed.	None	None	3.48	B1
T8	<i>Chamaecyparis lawsoniana</i> (Lawson Cypress)	M	140	8(3)	1	1	1	1	Poor	10+	Small heavily suppressed conifer set in old raised bed.	None	None	1.68	C1
T9	<i>Ilex aquifolium</i> (Holly)	M	100	7(2)	1	1	1	1	Fair	10+	Small garden ornamental set in old raised bed.	None	None	1.2	C1
T10	<i>Fagus sylvatica</i> 'Purpurea' (Copper Beech)	M	380	12(2)	6	5	5	5	Good	20+	Mature tree set in old garden raised bed.	Stem divides above 1.5m.	None	4.56	B1
T12	<i>Ulmus procera</i> (English Elm)	M	400	11(4)	4	4	4	4	Fair	20+	Set in boundary hedge to east of plot.	None	None	4.8	B1
T13	<i>Fraxinus excelsior</i> (Ash)	M	240	10(2)	4	3	2	3	Fair	20+	Set in boundary hedge to east of plot. Heavy ivy and climbing rose clad.	None	None	2.88	B1
T14	<i>Ilex aquifolium</i> (Holly)	M	180,150,90	9(5)	1	1	1	1	Fair	20+	Heavily suppressed small tree close to Eastern boundary.	Low vitality. Stem divides above 1.5m.	None	3.01	C1
T15	<i>Picea abies</i> (Norway Spruce)	M	360	14(2)	4	4	4	4	Fair	20+	Mature tree close to Eastern site boundary	None	None	4.32	B1
T16	<i>Chamaecyparis obtusa</i> (Hinoki cypress)	M	310	9(1)	3	3	3	3	Fair	20+	Ornamental conifer close to Eastern site boundary	None	None	3.72	B1
T17	<i>Picea abies</i> (Norway Spruce)	M	300	14(2)	4	4	4	4	Fair	20+	Mature tree close to Eastern boundary.	None	None	3.6	B1
T18	<i>Ulmus procera</i> (English Elm)	M	240	11(2)	3	3	3	3	Fair	20+	Small tree set in hedge on Eastern site boundary.	None	None	2.88	B1
H1	<i>Ligustrum ovalifolium</i> (Privet), <i>Prunus laurocerasus</i> (Cherry Laurel), <i>Crataegus monogyna</i> (Hawthorn), <i>Corylus avellana</i> (Hazel), <i>Ulmus procera</i> (English Elm), <i>Sambucus nigra</i> (Elder)	M	60	3(0.5)	1	1	1	1	Fair	20+	Boundary hedge, historically formally trimmed, now lapsed into wide and tall hedge. Privet stems shaded and declining. Some dying Elm stems. Laurel generally in good condition.	None	None	0.72	B1
T11	<i>Salix caprea</i> (Goat Willow)	Y	120,110,95,85,60	6(2.5)	2.5	2.5	4.5	4	Poor	<10	Small multistemmed tree, self set on a concrete slab with very limited prospects. Damaged to stem and roots.	Multiple stems at ground level. Mechanical Damage.	None	2.58	U
T19	<i>Crataegus monogyna</i> (Hawthorn)	M	200 250 100 100	8(1.5)	3	3	3	2.5	Good	20+	Good quality mature tree, originally set in ornamental garden rockery.	Stem divides below 1.5m. Included bark present in fork.	None	4.2	B1
H2	<i>Prunus laurocerasus</i> (Cherry Laurel)	M	75	3.5(0)	1.5	1.5	1.5	1.5	Fair	10+	Boundary hedge, historically formally trimmed, now lapsed.	None	None	0.9	C2
H3	<i>Crataegus monogyna</i> (Hawthorn), <i>Ilex aquifolium</i> (Holly), <i>Ligustrum ovalifolium</i> (Privet), <i>Fraxinus excelsior</i> (Ash)	M	75	5(2)	1.5	1.5	1.5	1.5	Fair	10+	Boundary hedge, historically formally trimmed, now lapsed.	None	None	0.9	C2
T20	<i>Fraxinus excelsior</i> (Ash)	EM	220	8(5)	2.5	2	1	1.5	Fair	10+	Small Ash stem set in boundary hedge to north of plot.	None	None	2.64	C1
T21	<i>Fraxinus excelsior</i> (Ash)	M	550	10(4)	3	5	7	5	Fair	10+	Significant mature tree, heavy ivy cladding on stem and into crown and extensive dead branches throughout crown.	Unable to inspect stem due to Ivy. Major deadwood in crown.	None	6.6	C1
T22	<i>Crataegus monogyna</i> (Hawthorn)	M	250	6(2)	2	2	2	1.5	Poor	10+	Small heavily suppressed tree on southern boundary.	Unable to inspect stem due to Ivy.	None	3	C1

T23	<i>Salix caprea</i> (Goat Willow)	M	240,200	7(2.5)	3	3.5	5	4	Fair	10+	Small suppressed tree.	None	None	3.74	C1
T24	<i>Prunus spinosa</i> (Blackthorn)	M	350,170	8(4)	0	4.5	5	3	Poor	10+	Heavily suppressed tree.	Ivy on tree. Decay present on stem. Stem divides below 1.5 m. Mechanical Damage. Broken branches in crown. Major deadwood in crown.	None	4.67	C1