



2 no. timber casement windows, approx o/all size 765 x 815mm, with fixed lower lights and top hung, outward opening top casement, behind rebate in external stone surround. Windows glazed with 18mm o/all sealed double glazed units. When fixing casements, isolate from masonry with dpc and mastic seal to masonry surrounds. Outer structural opening size to each window 715 x 800mm with nominal 150 x100mm stone reveals and lintels, part rendered over to replicate existing margins between render and stone. Cill moulding to be 100 deep x 150mm wide stone section projecting and weathered stone section to match existing. supply and fix 90mm on face and 100mm deep stone mullion between windows.

Take out existing window to Kitchen and cart away. Build up masonry approx. 250mm to level of new cill and extend opening to accommodate additional casement window. Utilise existing reveal blocks where possible and supply new stone mullion, lintel, and cill as described above. Reuse existing materials from demolitions as far as possible to build up to new levels. Make good render to approx. shaded area.

CHAUFFEURS LODGE, 5,BANK HALL COTTAGES SAWLEY: PART REAR ELEVATION (1:20 @ A4)