

FIRE ESCAPE DOOR SCHEDULE - LOWER LINE SHOWERS - FIRST FLOOR

FLOOR REF		DOOR REF	A	B	C	D	E	F	G	H	Comments
F/F	LOWER LINE SHOWERS	1	✓								Stairwell
F/F		2	✓								Corridor/Stairwell
F/F		3	✓							GD-F1	Dorm 1
F/F		4	✓								Services
F/F		5	OK								Corridor
F/F		6	✓							GD-F4	WC
F/F		7	✓							GD-F5	Bathroom
F/F		8	✓							GD-F5	Bathroom
F/F		9	✓							GD-F6	Dorm 3
F/F		10	✓								Corridor
F/F		11	✓								Store
F/F		12	✓							GD-F6	Dorm 7
F/F		13	✓							GD-F9	Dorm 6
F/F		14	✓							GD-F8	Dorm 4
F/F		15	✓							GD-F10	Dorm 5
F/F		16	✓								Corridor
F/F		17	✓							GD-F11	Dorm
F/F		18	✓							GD-F10	Dorm 5
F/F		19	✓								Corridor
F/F		20	✓							GD-F12	Bedsit
F/F		21	✓								Stairwell

A Provide rebated intumescent and smoke seals to the existing doors with either:

i) An Envirograf Product group 76 Rebated intumescent fire and smoke seals with aluminium holder (sheet 1)

II) An Envirograf Product group 100 Rebated intumescent fire and fire/smoke seals in two types (sheet 2)

B Repair with matching materials, split/damaged panels to panel doors re-using existing plants or made to match plants as req.d.

C Replace non fire resistant glazing with new Pyroglas (clear) or Georgian wired

D Upgrade, or replace ironmongery to suit door type and location, including o/h door closers.

E Adjust existing doors to form a regular seal to all edges

F Provide adequate signage on doors fit for purpose and use

G Replace the whole door including new ironmongery again, fit for purpose in both use and location of the door.

H English Heritage Conservation Report 2008 Room reference for Room location

glass dependant on location of door