

FIRE ESCAPE DOOR SCHEDULE - (MAGAZINE) - EAST WING - 3rd FLOOR

FLOOR REF		DOOR REF	A	B	C	D	E	F	G	H	Comments
	EAST WING	1	✓								Stairwell/Dorm 5
		2	✓								Stairwell
		3	OK								Corridor
		4	OK								Corridor
		5	Locked								Stairwell
		6	OK								Corridor
		7	OK							EW-T14	Bedroom
		8	OK							EW-T13	Bedroom
		9	OK							EW-T12	Bedroom
		10	OK							EW-T11	Bedroom
		11	OK							EW-T9 +	Bedsit
		12	OK							EW-T6	Study Area
		13	Locked								Bedsit
		14	Locked								Store
		15	OK							EW-T6	Study Area
		16	Locked							EW-T5	Bedsit
		17	OK							EW-T4	WC/Shower
		18	✓								Stairwell/Dorm 6
		19	OK								
			Locked doors to be re-checked								

A Provide rebated intumescent and smoke seals to the existing doors with either:

i) An Envirograf Product group 76 Rebated intumescent fire and smoke seals with aluminium holder (sheet 1)

II) An Envirograf Product group 100 Rebated intumescent fire and fire/smoke seals in two types (sheet 2)

B Repair with matching materials, split/damaged panels to panel doors re-using existing plants or made to match plants as req.d.

C Replace non fire resistant glazing with new Pyroglas (clear) or Georgian wired

D Upgrade, or replace ironmongery to suit door type and location, including o/h door closers.

E Adjust existing doors to form a regular seal to all edges

F Provide adequate signage on doors fit for purpose and use

G Replace the whole door including new ironmongery again, fit for purpose in both use and location of the door.

H English Heritage Conservation Report 2008 Room reference for Room location

glass dependant on location of door