

STONYHURST COLLEGE, CLITHEROE
FIRE ESCAPE DOOR SCHEDULE - L501

FLOOR REF		DOOR REF	A	B	C	D	E	F	G	H	Comments
GF	WEST WING	1	✓							WW-G3	Office (Strip in frame)
GF		2	✓							WW-G3	Office (Strip in frame)
GF		3	OK							WW-G4	Classroom
GF		4	✓							WW-G5	Classroom
GF		5	✓							WW-G6	Classroom
GF		6	OK							WW-G7	Office
GF		7	OK							WW-G7	Playroom
GF		8	OK								Staircase
GF		9	OK								Corridor
GF		10	OK							WW-G8	Syntax Playroom
GF		12				✓				WW-G9	Games Room
GF		13		✓						WW-G7	Playroom
GF		11	OK								Corridor
GF		14			Locked					WW-G10	Duty Flat
GF		15	✓							WW-G11	Bedroom
GF		16	✓							WW-G12	Bedroom
GF		17	OK								Corridor
GF		18	Locked							WW-G13	Showers
GF		19	OK								Store
GF		20	OK								Corridor

A Provide rebated intumescent and smoke seals to the existing doors with either:

i) An Envirograf Product group 76 Rebated intumescent fire and smoke seals with aluminium holder (sheet 1)

II) An Envirograf Product group 100 Rebated intumescent fire and fire/smoke seals in two types (sheet 2)

B Repair with matching materials, split/damaged panels to panel doors re-using existing plants or made to match plants as req.d.

C Replace non fire resistant glazing with new Pyroglas (clear) or Georgian wired

D Upgrade, or replace ironmongery to suit door type and location, including o/h door closers.

E Adjust existing doors to form a regular seal to all edges

F Provide adequate signage on doors fit for purpose and use

G Replace the whole door including new ironmongery again, fit for purpose in both use and location of the door.

H English Heritage Conservation Report 2008 Room reference for Room location

glass dependant on location of door