

STONYHURST COLLEGE, CLITHEROE
FIRE ESCAPE DOOR SCHEDULE - L504

FLOOR REF		DOOR REF	A	B	C	D	E	F	G	H	Comments
S/F	STUDY AREA	1	✓								Corridor
S/F		2	OK								Store
S/F		3	✓			✓					Corridor
S/F		4	OK							SF-09	Flat
S/F		5	✓							SF-09	Office (Strip set in frame)
S/F		6	✓							SF-09	Office (Strip set in frame)
S/F		7	✓								Bridge of Sighs
S/F		8	✓								Showers (Strip set in frame)
S/F		9	✓							SF-S11	Stairs (Strip set in frame)
S/F		10	OK							SF-S11	Study Area
S/F		11	✓							SF-S11	Flat
S/F		12	✓							SF-S10	Showers (Strip set in frame)
S/F		13	✓							SF-S11	Corridor
S/F		14	OK							SF-S11	Study Area
S/F		15	OK							SF-S11	Staircase
S/F		16	Locked							SF-S11	Office
S/F		17	✓							SF-S12	Showers (Strip set in frame)
S/F		18	✓							SF-S11	Corridor (Strip set in frame)
S/F		19	OK							SF-S11	Study Area
S/F		20	Locked							SF-S11	Office
S/F		21	OK							SF-S11	Study Area
S/F		22	✓							SF-S11	Stairs (Strip set in frame)

A Provide rebated intumescent and smoke seals to the existing doors with either:

i) An Envirograf Product group 76 Rebated intumescent fire and smoke seals with aluminium holder (sheet 1)

II) An Envirograf Product group 100 Rebated intumescent fire and fire/smoke seals in two types (sheet 2)

B Repair with matching materials, split/damaged panels to panel doors re-using existing plants or made to match plants as req.d.

C Replace non fire resistant glazing with new Pyroglas (clear) or Georgian wired

D Upgrade, or replace ironmongery to suit door type and location, including o/h door closers.

E Adjust existing doors to form a regular seal to all edges

F Provide adequate signage on doors fit for purpose and use

G Replace the whole door including new ironmongery again, fit for purpose in both use and location of the door.

H English Heritage Conservation Report 2008 Room reference for Room location

glass dependant on location of door