

Proposed alterations
13 Moor Lane
Clitheroe

Scale 1:50

All work to be to satisfaction
of local authority.

320130277P

Existing stone wall?
Vertical stone chabim.

Notes:
Existing windows to first and
second floor to be replaced in
UPVC - 80/20 frames with min
u value 1.6 w/m²k.
Min U-value of glass windows
to be 0.83 w/m²k.
Timber fascia & plaster to be
replaced.
All timberwork to be re-painted
in 2 coats of exterior paint to match
to match existing.

