

SD 75 SW

EASINGTON

10/41

Standridge Farmhouse and farm
building adjoining to south

II

House, 'R^CM 1763' on 1st floor plaque. Squared watershot sandstone with stone slate roof. Double-pile plan with central entry and end stacks. 2 storeys, 2 bays. The windows are tripartite with plain stone surrounds and square mullions. The door has a plain stone surround. To the left is an agricultural unit having a re-used one-light window with inner hollow chamfer and outer chamfer. To its right is a door surround of re-used C17th dressings, partly moulded and partly chamfered. At the rear of the house is a tall stair window with plain reveals and 3 transoms, 3 2-light windows with square mullions, and a plain stone door surround.

SD 75 NW

EASINGTON

5/42

Stephen Park

GV

II

House, 'I^HA 1700' over door lintel. Slobbered rubble with slate roof, the left-hand stack having a brick cap. Double-pile plan with end stacks. 2 storeys, with a large central porch of 1½ storeys. The upper porch storey oversails on a string course on the front and left-hand return walls. To each side of the porch are mullioned windows with an inner ovolo moulding and outer chamfer and a hood; to the left one of 4 lights, to the right one of 3 lights. To the left on the 1st floor are the remains of a similar surround, now forming part of the jambs to a tall sashed window. To its right, above the porch, is a window with plain reveals. To the right of the porch is a 5-light window with an outer chamfer and inner hollow chamfer. The porch window, above the door, is of 2 lights with an outer chamfer and inner cyma moulding. Its right-hand return wall has a small fixed window with glazing bars and the remains of double-chamfered jambs. The left-hand return wall has a similar window with plain reveals. The outer porch doorway has a moulding which continues across the lintel in a zig-zag pattern. A drip mould rises over the lintel and over the date plaque. The inner porch doorway is chamfered with a debased 4-centred head and decoration and date on the lintel, now obscured by paint. The rear (north) wall has ground-floor mullioned windows with outer chamfer and inner ovolo moulding, of 2 lights, one light (formerly larger), and 5 lights. On the 1st floor are the remains of surrounds with outer chamfer and inner hollow chamfer. Inside, the left-hand front room has a wide moulded segmental-arched fireplace, now partly blocked. Stair and 1st floor not accessible at time of survey.

SD 75 NW

EASINGTON

5/43

GV

768 559
Barn to west of Stephen Park

II

10/9/92

Barn, 'I^HP 1736' on plaque in east wall. Slobbered rubble with stone slate roof. Wider at the south end, where there is an underhoused shippon, with a 2nd shippon at the north end. The east wall has a wide entrance with long-and-short jambs and an arched head of 2 pieces of stone. At the far right is a door with long-and-short jambs. At the far left is a similar door, now blocked. The gables have copings and shaped kneelers. The south wall has 2 shippon doors with plain reveals. At the rear (west) is a blocked threshing door and later additions. Inside are the remains of cattle stalls at both ends, now partly destroyed. The roof trusses, from south to north, are as follows. 1. A tie beam with curved queen struts, and a short king post rising from a collar. 2. A tie beam with curved queen struts, the principals curved to meet a king block which is shaped at the bottom. 3. A tie beam with curved queen struts, and a king block, shaped at the bottom. 4. A softwood truss with tie beam, straight queen struts, and a king block.
