

SD 75 39

PENDLETON

PENDLETON VILLAGE (SOUTH SIDE)

11/129

Spring House Farmhouse and barn
adjoining to west

GV

II

House, early C17th. Sandstone rubble with roof of imitation stone slates. 2 storeys. North wall has 5-light double-chamfered mullioned window at left. At the right is a window with reconstructed double-chamfered surround, and hood. To its left is a blocked doorway with chamfered surround. On the 1st floor is a 2-light window with plain stone surround and square mullion. To its left are 2 one-light blocked chamfered windows. To its right are 2 similar windows, the left-hand one at a lower level. The south wall is of 3 bays, having windows with plain stone surrounds and square mullions, of 2 lights, 3 lights and 2 lights. The door, to the right of the first bay, has a plain stone surround. Interior. The room to the right of the present doorway has a massive firehood bressumer, chamfered with lambs-tongue stops. The two axial main ceiling joists are also chamfered and stopped. The east wall of the room is formed by a plank-and-muntin partition, the muntins having scribed mouldings. At each side of the partition are doorways into the 2 eastern rooms, each with a plank door and with a Tudor-arched head having an incised cross above the apex of the arch. The eastern rooms are separated by a similar partition.

The barn, probably, of early C19th date, has a roof of stone slate, and a north wall which continues the line of the house. It has a wide entrance with a segmental arch of punched voussoirs, and a window to the right with a concrete surround.

SD 75 39

PENDLETON

PENDLETON VILLAGE (SOUTH SIDE)

11/130
13.2.1967
GV

Stork House

II

House, 1840. Squared sandstone with stone slate roof. 2 storeys. North-west gable wall, facing down village street, of one bay. Windows tripartite with chamfered stone surrounds, splayed mullions, and hoods. The door, to the right, has a chamfered stone surround with hood. Under the apex is a plaque with ogee hood, inscribed 'LGNS 1840'. 2 chimneys on ridge and one on left-hand return wall. The left-hand return wall has a window on each floor with plain stone surround, and a door with similar surround to their right. Listed for group value only.