

BASHALL EAVES

SD 74 SW

10/6

16.11.1954

GV

5/12/19
Barn, approx. 60 metres south
of Bashall Hall

II

Barn, probably early C18th with later alterations. Sandstone rubble with stone slate roof. North-east wall has a wide entrance with long-and-short jambs and external sliding door. At the far right is a smaller doorway with similar external door. To the left are 2 windows with plain stone surrounds, and a pitching door above with plain reveals. The gables have copings with re-used crocketed finials at the apex. The north-west wall has 2 windows with long-and-short jambs. Above are chamfered ventilation slits, and, below the apex, a circular pitching hole with plain stone surround. The south-east wall has 3 similar pitching holes. At the rear is a later lean-to. Inside are bolted queen-post trusses. The south-east wall is shown in a drawing of Bashall Hall c.1720, Samuel Buck's Yorkshire Sketchbook, Reproduced in Facsimile, Wakefield, 1979.

BASHALL EAVES

SD 74 SW

10/7

-
GV

10/8/19
Bridge approx. 15 metres north
of farm building to north of
Bashall Hall

II

Bridge over Bashall Brook, possibly early C19th. Sandstone rubble. Single segmental arch, and solid parapets with flat copings.

SD 710 423

BASHALL EAVES

SD 74 SW

10/5
16.11.1954
GV

Bashall Hall

II*

House, probably c.1600 with early C18th alterations, but with detailed development unclear. Sandstone rubble with stone slate roof. Comprises an east block of 3 storeys with attics with its main roof running east-west and with 2 gables on each side facing north and south. To the west is a central block, said to be reduced in height after a fire, of 2 storeys with the roof running north-south. The main roof of the adjoining west wing is parallel. This wing projects towards the south and is of 2 storeys, formerly with attic. The early windows have an outer chamfer and inner hollow chamfer, and hoods. The main facade faces south. Under the right-hand gable of the east block the ground floor has a 12-light mullioned and transomed window with king mullion, now cut into by a later window. On the 1st floor is a 12-light mullioned and transomed window. On the 2nd floor are 2 similar windows of 6 lights each. Above is a blocked oculus. Under the left-hand gable on the ground floor is a 5-light mullioned window and a door with plain reveals. On both the 1st and 2nd floors are 3 sashed windows with glazing bars and stone surrounds with a shallow cyma moulding. Above both sets of windows is a deep plain stone band. Under the gable is a blocked oculus matching the one to the right. The central block has mullioned windows on the ground floor. The 1st floor has sashed windows with glazing bars and architraves. Between them is a doorway reached by external stone steps. It has an architrave with bolection moulding and a broken segmental pediment on console brackets. Above is a cartouche. Below the gable is a plain stone band, with a blocked oculus above. The west wing has a 4-light mullioned window on the ground floor, a 14-light mullioned and transomed window on the 1st floor and a blocked attic window. Its right-hand return wall has a blocked chamfered doorway with Tudor-arched head. The north wall has a buttress with moulded offsets towards the left (east). Further right, on the 1st floor of the east block, is a doorway, now a window, with a surround chamfered in two orders with a Tudor-arched head. Further right, in the central block, is a large canted bay window, with a 3-light mullioned window on the ground floor, which is otherwise blank, and continuous glazing on the 1st floor, with 2 transoms. Interior. The eastern ground-floor room has ovolo-moulded main ceiling beams and 2 chamfered stone doorways with Tudor-arched heads. Further west, in line with the 1st floor doorway visible on the outside of the north wall, is a dog-leg stair with its 2nd flight of stone, and with the 1st floor landing partly carried on a moulded stone arch. The barley-sugar balusters and ramped handrails are probably a C18th addition. On the 1st floor the eastern room has panelling mostly of an early C17th type. The room adjoining to the west, on the south side, has panelling of an early C18th type, with raised panels and bolection mouldings. The central block has a room with 2 chamfered doorways with Tudor-arched heads and a moulded fireplace with Tudor arch, taken from elsewhere in the house. The west wing, presently being restored and open to the roof on the 1st floor, has trusses of a steep pitch with tall king posts rising off tie beams and with queen struts. Buck's drawing of c.1720, labelled 'The East Prospect of Bashall The Seat of William Ferrers Esq.,' shows the south front almost as it appears today. A low building to the right may be a demolished east wing, or the retainers' building (q.v.) behind the house. Samuel Buck's Yorkshire Sketchbook, Reproduced in Facsimile, Wakefield, 1979.