

SD 63 NE

RIBCHESTER

CHURCH STREET

8/139

Nos. 25 and 26

GV

II

Pair of weavers' houses, part of a row, late C18th. Squared sandstone with slate roof. 3 storeys with plain frieze and stone gutter brackets. Windows have plain reveals. Each house has a door to the left with plain stone surround and triangular moulded hood on shaped stone brackets. The attic to No. 25 retains its sashed window with glazing bars. No. 26 has a tunnel entrance to the left with plain stone surround with semi-circular head, projecting key and imposts. A 1st floor window has been inserted over the tunnel entrance.

SD 63 NW

RIBCHESTER

CHURCH STREET

7/140

Nos. 28 & 29

11.11.66

GV

II

Pair of houses, 1745. Brick with sandstone dressings and slate roof. 2 storeys. Plinth, string course, chamfered quoins and moulded cornice gutter all of stone. No. 29, to the right, of 3 bays with central door. No. 28, to the left, of one bay with the door to the right. The windows have architraves, those on the ground floor having raised and fielded panels carved on aprons. The windows to No. 29 are sashed with glazing bars. Those to No. 28 are modern. Both doorways have architraves and cornices, that to No. 29 having a raised and fielded panel carved on its frieze. The right-hand gable has a stone chimney cap, the left-hand gable a modern cap. Between the houses is a brick cap, set forward of the ridge. At each end of the facade is a lead downspout with 'E I 1745' cast on each hopper.
