

SD 74 SW

PENDLETON

SD 747 402

6/116
29.12.1952
GV173/18/192
Standen Hall

II*

Country house, rebuilt 1757 (VCH) with west wing rebuilt c.1858. Squared sandstone with slate roofs. East front a symmetrical composition of 3 storeys and 7 bays, with projecting quoins, a string course above the 1st floor and a cornice. The central 3 bays on the ground floor project to carry an attached giant order of Doric columns supporting an entablature with triglyph frieze and a dentilled moulded pediment. Windows sashed, with glazing bars on the 1st floor and to the 3 right-hand bays of the 2nd floor, the remainder sashed with no glazing bars. All have architraves, the 3 central 1st floor ones with pulvinated friezes and pediments, the central one segmental. The central doorway has Tuscan pilasters, a semi-circular head, and a pediment on console brackets. 2 chimneys on ridge. Adjoining to the right is a 2-storey 3-bay wing in a similar style. Adjoining its front wall at right angles is the single-storey billiard room of 1876. The south front has, at its right-hand side, 2 bays of the 3-storey east block, the 2nd floor above a cornice. Towards the centre of the facade is a recessed 2-storey section of 3 bays in a similar style, with a central doorway with architrave, and pediment on console brackets. The doorway is within an open Adamesque porch with corner urns. To the left are 3 bays of the taller 2-storey 1858 wing, whose details are more Italianate on the west side. Interior appears to have been re-modelled in C19th. North room at front of east block has pedimented oak doorcases. Door in east front now enters under a stair with stick balusters and ramped handrail. 1st floor rooms not accessible at time of survey.

SD 74 SW

PENDLETON

6/117
-
GV23/5/92
Mounting block approx. 40 metres south
of south front, Standen Hall

II

Mounting block, possibly early C19th. Sandstone. Symmetrical, with 6 steps on each side. Treads have nosings and are each carved from one piece of stone.

1.
5295

SD 725 404

HENTHORN ROAD
(West Side)
Siddows Farmhouse

SD 74 SW 7/52 19.5.50.

II

2.
Early C18. 2 storeys in rubble. The door is plain with a chamfered lintel and has probably been widened. 2 windows per storey, 1 of 4 lights and 1 of 3 lights still of C17 type. Over the door and the ground floor windows are dripstones of considerable projection. A square panel over the door is inscribed T W (over) 1707 I F.

1.
5295

SD 729 403

HIGHER STANDEN
The Old Bothy

SD 74 SW 7/54 19.5.50.

II

2.
C17 and C18. 2 storeys in rubble. The C17 portion is lower and retains 1 early C17 window of 6 lights. The remaining windows are C18. In the C18 portion on the left are 2 Venetian windows, 1 per storey, with plain keystones to the arched centre lights.

1.
5295

SD 742 408

LITTLE MOOR
(North-East Side)
Nos 1 to 9 (odd)

SD 74 SW 7/45

II

GV

2.
Terrace of small C18 or early C19 houses of 2 storeys, roughcast. Nos 1 and 3 have 4 windows, hung sashes with glazing bars, above 2, and 1 rectangular window to No 3. 2 doors of 6 fielded panels with glazed rectangular fanlights, stone pilasters and cornice. Nos 5 and 7 have 3 windows, stone surrounds. Door to No 5 of 6 fielded panels with round-arched glazed fanlights, keystone and impost bands, stone surround to door of No 7. No glazing bars to No 7. No 9 has main elevation to end. 2 windows flank 2 small windows. 3 windows to ground, no glazing bars. Cement surround, modern door. Pented extension to rear.

Nos 1 to 15 (odd) and Little Moor House form a group.

1.
5295

SD 742 408

LITTLE MOOR
(East Side)
Nos 11 to 15 (odd)

SD 74 SW 7/44

II

GV

2.
Three C18 or early C19 cottages, No 11 behind the others and rendered, with 2 windows with lintels and modern glazing, above 1. Door in stone surround. No 13 has 2 windows above 1 and door with semi-circular fanlight, modern door. No 15 has 2 windows over 2, plain stone surround to modern door.

Nos 1 to 15 (odd) and Little Moor House form a group.

1.
5295

SD 742 408

LITTLE MOOR
(West Side)
Little Moor House

SD 74 SW 7/46

19.5.50.

II

GV

2.
Late C18 or early C19. 2 storeys, stuccoed. In the south elevation is a 2-storey bow, with a canopy to the ground floor. The semi-circular headed doorway has a small pediment over. There is a 2-light window and 1 of 3 lights, with a French window in the ground storey and 4 single-light windows in the upper storey. Glazing bars only to rear elevation.

Nos 1 to 15 (odd) and Little Moor House form a group.

1.
5295

SD 745 413 CA

LOWERGATE (negative)
(North-East Side)

SD 7441 1/240

II

GV

2.
C18 origins. 2 storeys, pebble dashed, with Welsh slate roof and rusticated quoins. 3 windows to 1st floor, stone surrounds, no glazing bars. Ground floor has 2 C19 windows of 2 lights in chamfered reveals and 1 in stone surround. Late C19 doorway with carved spandrels, moulded cornice. To right, smaller doorway with plain pilasters and cornice, rectangular fanlight. Rendered plinth. 3 stone stacks.

Dog and Partridge Public House and No 3, The Towns Well and Nos 5 to 9 (odd) form a group No 5 being a building of local interest only.