

CLITHEROE GRAMMAR SCHOOL - SPORTS HALL

SPECIFICATION OF MATERIALS

Pitched Roof: Aluminium Standing Seam

Manufacturer and reference: Ash & Lacy Building Systems Ltd
Profile reference: Ashzip 400 with Rain noise reduction membrane bonded to reverse of Ashzip sheet
BBA certificate number 06/4301
Nominal thickness/gauge: 0.9mm. Alloy 3000 series
External finish: ARS (Abrasive resistant system).
Colour: RAL Colour **7039 Quartz Grey**

Fascia and soffits

Manufacturer and reference: Ashfab secret fix joint fascias by Ash and Lacy Building Systems Ltd
Material: Aluminium minimum grade 1050A H14 Thickness/gauge: Generally 2mm minimum thickness . Note that a high aesthetic standard is required.
Finish/Colour: Polyester powder coated finish, colour ref RAL **7039 Quartz Grey**

Rain water pipes

Manufacturer and reference: Ash and Lacy Building Systems Ltd
Material: Aluminium minimum grade 1050A H14 Thickness/gauge: Generally 2mm minimum thickness .
Finish/Colour: Polyester powder coated finish, colour ref RAL **7039 Quartz Grey**

High level wall cladding:

Manufacturer(s): Ash & Lacy Building Systems Limited
Rainscreen cladding system: Ashtech Freedom 1
Type: Ventilated
Rainscreen Panel
Type: Cassette
Material: ACM
Thickness: 4.0 mm
Finish/colour: PvdF Colour **7039 Quartz Grey**



Typical image only

Curtain Walling and Windows:

Polyester powder coated aluminium (Colour: RAL **7039 Quartz Grey**)

Doors:

Solid core timber doors painted grey

Facing Brickwork to building generally:

Manufacturer: IBSTOCK BRICK ROYSTON GOLDEN BUFF drag faced wire cut with matching tilcon mortar.



Brickwork to feature panels either side of entrance door:

Manufacturer: IBSTOCK BRICK STAFFORDSHIRE BLUE A2221 A drag faced wire cut with matching tilcon mortar.



External landscaping

COATED MACADAM PAVING:

Granular sub-base: [MOT type 1 Stone in accordance with the Specification For Highways Works]..

- Thickness: [200mm].

Binder course: [20mm size dense binder course to BS 4987 : Part 1 with 150, 200, 300 pen bitumen or C 38 tar.].

- Thickness: [45mm].

Surface course: [6mm size dense surface course to BS 4987 : Part 1 with 100 or 200 pen bitumen binder.].-

Thickness: [20mm].

Surface treatment: [Close graded].

**CONCRETE COBBLES TO PERIMETER OF BUILDING AND FEATURE STRIPS
IN PAVED AREA**

Marshalls plc.

Product reference: Tegula Concrete cobbles.

Colour: Pennant grey.

Sizes: 80x80mm - 60 mm thick laid in 3 rows

Fencing: 1100mm steel hooped fence paint finish (Colour: RAL -**7039 Quartz Grey**)

Grassed areas: All new / affect grassed areas to be turfed